



# West Roofing Systems Inc.

75	23
70	27
65	30
60	34
	38
	41

## Medical Facilities

This Illinois Hospital had 7,400 square feet of scalloped concrete roof deck with an existing smooth surface modified bitumen. Specifications called for removal of approximately 50% of the existing roof system that was saturated and installation of 3" SPF with 20 mils of silicone coating and granules.

The 3" of SPF provides an approximate R-value of 20, and the fluid applied self-flashing foam fit perfectly for the roof configuration.

With an SPF roof, there was no need for costly counter flashings or perimeter edge material.

For more information call:  
 Jack Moore  
 800-356-5748 x102  
 jackm@westroofingsystems.com  
 Job #23118



This scalloped hospital roof received a 10 year manufacturers warranty.



"Before" picture of scalloped roof.



"Before" picture of aged valley in roof.



"After" picture of drain and vent stack in valley.

121 Commerce Drive  
 PO Box 505  
 LaGrange, OH 44050

Phone: 800.356.5748  
 Fax: 440.355.8106  
 www.westroofingsystems.com